# FEDERAL COMMUNICATIONS COMMISSION

CLASS OF	STATION	FM
----------	---------	----

				CLA	SS OF STATIO	DN
ST	FILE	The follow	wing applic	cation is submitted f	-	e Chief, Broadcast Bureau. NATURE OF APPLICATION
OR	BPED	-920630ME N/M	KSKF 90.9MHZ	ST OF OR ACT BY S' KLAMATH FALI		ED CP TO MAKE CHANGES: ERP: 6.5 KW (H) 2.00 KW (V)
			WLO-417 WLO-415 WLO-420	KLAMATH FALLS ASHLAND KLAMATH FALLS	OR OR OR	
		KPIRATION [ 7-9-9		·		CHIEF, LICENSE DIVISION
RECO		IDATION: G		CONSTRUCTION	DATES, STAR	RTEND
			<u>,</u>			

**APPROVED** 

FOR CHIEF, BROADCAST BUREAU

F.C.C.-WASHINGTON, D.C.

STATE BOARD OF HIGHER EDUCATION OFFICE OF THE SECRETARY P.O. BOX 3175 EUGENE, OREGON 97403 (503) 346-5795

June 23, 1992

RECEIVED Ms. Donna Searcy, Secretary JUN 3 0 1992

Federal Communications Commission 1919 M Street NW Washington, DC 20554

FEDERAL COMMUNICATIONS COMMISSION OFFICE OF THE SECRETARY

BMPED-88415MC RE: Klamath Falls, OR

KSKF

Dear Ms. Searcy:

On behalf of the State of Oregon Acting By and Through the State Board of Higher Education and for Southern Oregon State College, I am submitting two copies of FCC Form 340 requesting authority to increase the operating power of station KSKF(FM), Klamath Falls, OR.

I certify that KSKF operates as a non-commercial educational station, in accordance with 73.503 of the Commission's males and that the broadcast services reported upon herein will becaused solely on a non-commercial educational basis.

I claim exemption from any applicable fees under section 1.1112(d) of the Commission's rules.

Cordially,

Wa rrainia L. Thompson

Secretary of the Board

VLT:vs

Enc.

Arter & Hadden cc: Jerry Casby Ronald Kramer

Approved by OMB 3060-0034 Expires 11/30/94 See Page 23 for information regarding public burden estimate

### APPLICATION FOR CONSTRUCTION PERMIT FOR NONCOMMERCIAL EDUCATIONAL BROADCAST STATION

(Carefully read instructions before filing form)

Return only form to FCC

RECEIVED

For Commission Use Only ADED DONIST ME

1. Name of Applicant State of Oregon Actin the State Board of Hi for Southern Oregon S	gner Educati	ion and Name	Virginia Tho	mpson, Secreta of Higher Educ	ry
Street Address or P.O. Box P.O. Box 3175		Stree	P.O. Box 317		
City	State OR	ZIP Code City 97403		State OR	<b>ZIP Code</b> 97403
Eugene Telephone No. (Include Area Code) (503) 346-5796			Eugene No. (Inclede Ar (503) 346-57	es Codel	37403
This application is for:	AM	$\overline{\mathbf{x}}$	FM	Tv Tv	
(a) Channel No. or Frequency		(b) Principal	City		State
90.9 FM		Community	Klamath Fal	ls	OR
MINOR change in license			<u>SKF</u>		
	ed facilities; call	sign:			······································
MINOR change in license	ed facilities; call construction permit:	sign:			·- · · · · · · · · · · · · · · · · · ·
MINOR change in license  MAJOR modification of  File No. of construction	construction permit:	sign:			······································
MINOR change in license  MAJOR modification of  File No. of construction  MINOR modification of	construction permit:  construction permit:	sign:			······································
MINOR change in license  MAJOR modification of  File No. of construction  MINOR modification of  File No. of construction	construction permit:  construction permit:  construction permit:  application; applicuse this form to	sign:  nit; call sign:  nit; call sign:  cation file number:	filed application. Sh	ould you do so, how	
MINOR change in license  MAJOR modification of  File No. of construction  MINOR modification of  File No. of construction  AMENDMENT to pending  NOTE: It is not necessary to a	construction permit:  construction permit:  construction permit:  application; application to other portions of	sign:  nit; call sign:  nit; call sign:  sation file number:  amend a previously of the form that con	filed application. Sh	ould you do so, how	
MINOR change in license  MAJOR modification of  File No. of construction  MINOR modification of  File No. of construction  AMENDMENT to pending  NOTE: It is not necessary to a submit only Section I and those	construction permit:  construction permit:  construction permit:  application; application to other portions of	sign:	filed application. Sh	ould you do so, how	vever, please
MINOR change in license  MAJOR modification of  File No. of construction  MINOR modification of  File No. of construction  AMENDMENT to pending  NOTE: It is not necessary to a submit only Section I and those	construction permit:  construction permit:  construction perm permit:  application; applic use this form to other portions of	sign:	filed application. Sh	ould you do so, how	vever, please

BPED -920630ME KSKF KLAMATH FALLS OR ST OF OR ACT BY ST BOARD OF HIGH EL

February 1992

#### SECTION VI - EQUAL EMPLOYMENT OPPORTUNITY PROGRAM

1.	Does the applicant propose to employ five or more full-time employees?	Yes	XX No
	If Yes, the applicant must include an EEO program called for in the separate Broadcast Equal Employment Opportunity. Program Report (FCC 396-A).		
SE	CTION VII - CERTFICATION		
1.	Has or will the applicant comply with the public notice requirements of 47 CF.R. Section 73.3580?	XX Yes	□ No
2.	By checking Yes, the applicant certifies that, in the case of an individual applicant, he or she is not subject to a denial of federal benefits that includes FCC benefits pursuant to Section 5301 of the Anti-Drug Abuse Act of 1988, 21 U.S.C. 862, or, in the case of a non-individual applicant (e.g., corporation, partner ship or other unincorporated association), no party to the application is subject to a denial of federal benefitat includes FCC benefits pursuant to that section. For the definition of a "party" for these purposes, see 47 C.F.R. Section 1.2002(b).	- Ins	<u></u> №
	The ABB MARK have been a state of the same of the control of the same of the s		

The APPLICANT hereby waives any claim to the use of any particular frequency as against the regulatory power of the United States because of the previous use of the same, whether by license or otherwise, and requests an authorization in accordance with this application. (See Section 304 of the Communications Act of 1834, as accorded.)

The APPLICANT acknowledges that all the statements made in this application and attached exhibits are considered material representations, and that all exhibits are a material part hereof and incorporated herein.

The APPLICANT represents that this application is not filed for the purpose of impeding, obstructing, or delaying determination on any other application with which it may be in conflict.

In accordance with 47 C.F.R. Section 1.65, the APPLICANT has a continuing obligation to advise the Commission, through amendments, of any substantial and significant changes in information furnished.

WILLFUL FALSE STATEMENTS MADE ON THIS FORM ARE PUNISHABLE-BY FINE AND/OR IMPRISONMENT (U.S. CODE, TITLE 18, SECTION 1001), AND/OR REVOCATION OF ANY STATION LICENSE OR CONSTRUCTION PERMIT (U.S. CODE, TITLE 47, SECTION 312(a)(1)), AND/OR FORFEITURE (U.S. CODE, TITLE 47, SECTION 503).

I certify that the statements in this application are true and correct to the best of my knowledge and belief, and are made in good faith.

Name of Applicant State of Oregon Acting by and Through the State Board of Higher Education	Segretary of the Board
Signature Market	Date 23, 1992

# FCC NOTICE TO INDIVIDUALS REQUIRED BY THE PRIVACY ACT AND THE PAPERWORK REDUCTION ACT

The solicitation of personal information requested in this application is authorized by the Communications Act of 1934, as amended. The Commission will use the information provided in this form to determine whether grant of this application is in the public interest. In reaching that determination, or for law enforcement purposes, it may be necessary to refer personal information contained in this form to another government agency. In addition, all information provided in this form will be available for public inspection. If information requested on the form is not provided, processing of the application may be delayed or the application may be returned without action pursuant to the Commission's rules. Your response is required to obtain the requested authority.

Public reporting burden for this collection of information is estimated to vary from 78 to 302 hours 20 minutes with an average of 171 hours 36 minutes per response. These estimates includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, can be sent to the Federal Communications Commission, Information Resources Branch, Room 416, Paperwork Reduction Project, Washington, D.C. 20554, and to the Office of Management and Budget, Paperwork Reduction Project (3060-0034), Washington, D.C. 20503.

THE FOREGOING NOTICE IS REQUIRED BY THE PRIVACY ACT OF 1974, P.L. 93-578, DECEMBER 31, 1974, 5 U.S.C. 552s(e)(3), AND THE PAPERWORK REDUCTION ACT OF 1980, P.L. 96-511, DECEMBER 11, 1980, 44 U.S.C. 3507.

Section	V-B - FM	I BROADCAST E	INGINEERING	DATA	FOR COMMISSION FILE NO.  ASB Referral D  Referred by			-
Name of App	licant			<del></del>				
	STATE C	of OREGON ACT	ING BY AND	THROUGH TH	e State Boar	D OF HIGHER	EDUCATION	
Call letters /	if issued?		is this app	olication being	filed in response	to a window?	Yes [3	X No
	KSKF		if Yes, sp	ecify closing (	date:			
Purpose of A	pplication: 1	check epprepriate	bes(ex))	······································			<del></del>	<del></del>
Cons	truct a new (	main) facility		Coi	nstruct a new aux	ciliary facility		
Modi	fy existing co	enstruction permit	for main facility	Mo	dify existing cons	struction permit f	or auxiliary fac	;ility
Modi	fy licensed m	ain facility		Mo	dify licensed auxi	liary facility		
If purpose is	to modify, in	dicate below the	nature of change(	s) and specify	the file number(s	) of the authoriza	itions affected	1.
Anter	nna supporting	g-structure height		X Eff	ective radiated po	ower .		
Antei	nna height abd	ove average terrain	1	Fre	quency			
Anter	nna location			Cla	ss ·			
. Main	Studio locatio	on		O11	ner (Summerize br.	iefly?		
File Number	er(s) <u>BPED-</u>	-870121MB, BM	MPED-880415M	C AND BLED	-890821KA			
Channel No.	<del></del>	Principal	community to be	served:		Class I check	nly one box bet	/ <i>••</i> /
215	City KL/	AMATH FALLS	County	LAM A TH	State OR	□ A □ C2 X	C1	
(a) Specify STUKE	L MOUNTAIN	na.  county and state.  N, 18.5 KM FR  ates (to nearest seconds)	ROM KLAMATH	FALLS, ORE	GON ON A BEA	ARING OF N14	1E DEGREES	of array.
		be presumed.						
Latitude	42	05	50	Longitude	121	37	59	•
3. Is the supp	=	are the same as th	nat of another sta	ation(s) or prop	posed in another .	pending	X Yes	□ No
If Yes, gw	e call letter(s)	) or file number(s)	) or both.	KLAD-F	M, KDKF (T)	/) AND KFTS	(TV)	
		thange in height of and lighting, if an	•		-	pove ground level	including anter	nna,
				NO	CHANGE			

Latitude 0	" Longitude 0		-	
5. Has the FAA been notified of the prop If Yes, give date and office where no determination, if available.  Date JUNE 16, 1992	posed construction?  Itice was filed and attach as an Exhibit a copy of FA  NORTHWEST MOUNTAIN RE  Office where filed RENTON, WASHINGTON		Exhibit	
6. List all tanding areas within 8 km of al runway. None WITHIN 8 km. Landing Area	ntenna site. Specify distance and bearing from structu		est point of t	
(a) KINGSLEY FIELD, OR	9.0		N302E	
(b)				
7. (a) Elevation: Ite the neerest meter?				
(1) of site above mean sea level;	•	_	1961.1	_ meters
(2) of the top of supporting struct appurtenances, and lighting, if a	ture above ground (including antenna, all other		49.7	meters
	ture above mean sea level [(aX1) + (aX2)]	•	2010.8	_ meters
(b) Height of radiation center: Ite the	neerest meter). H = Horizontal; V = Vertical			
(1) above ground			43.3	_ meters ()
			43.3	_ meters (
(2) above mean sea level [ (aX	1) + (6)(1)]	•	2004.4	_ meters 0
			2004.4	meters (
(3) above average terrain		•	686.7	_ meters (
			686.7	_ meters (
in Question 7 above, except item 7(b)	supporting structure, labelling all elevations required X3). If mounted on an AM directional-array element, array towers, as well as location of FM radiator.		Exhib E-	i No.
9. Effective Radiated Power: (a) ERP in the horizontal plane	6.50	kw (HII)	2.00	kw (VII)
(b) is beam tilt proposed?		· · · · · · · · · · · · · · · · · · ·		es X No
If Yes, specify maximum ERP in the elevational plot of radiated field.	ne plane of the tilted beam, and attach as an Exhibit	a vertical	Exhib	A No.
#Polarization				

10. Is a directional antenna proposed?				Yes X No
If Yes, attach as an Exhibit a statement with plot(s) and tabulations of horizontally and verifield.			•	Exhibit No.
11. Will the main studio be located within the 70	dBu or 3.16 mV/	m contour?		Yes X No
tf No, attach as an Exhibit justification pursuan	t 10 47 C.F.R. Sec	tion 73.1125.		Exhibit No.
ON FILE, BPED-870121MB, No CHAN	IGE.			
12. Are there: (a) within 60 meters of the printransmitters, or any nonbroadcast lescept city blanketing contour, any established commen facilities, or populated areas; or (c) within ten or authorized FM or TV transmitters which management.	tizens band er and cial or governmen n (10) kilometers	oteur/ radio stations; cont receiving stations, of the proposed anten	or (b) within the cable head-end ha, any proposed	Yes No
If Yes, attach as an Exhibit a description of a steps to be pursued if necessary, and a stater objectionable interference (including that caus facilities in existence or authorized or to rad 47 C.F.R. Sections 73.315(b), 73.318(d) and 73.	ment accepting full ed by receiver-ind io receivers in use	responsibility for the duced or other types of	alimination of any of modulation) to	Exhibit No. E-2
13. Attach as an Exhibit a 7.5 minute series U.S. clearly, legibly, and accurately, the location of with the requirements set forth in instruction display the original printed contour lines and bear a scale of distance in kilometers.	the proposed trand	nsmitting antenna. This r Further, the map must (	nap must comply clearly and legibly	Exhibit No. E-3
14. Attach as an Exhibit (name the source) a map original printed latitude and longitude markings		• • •	ely, and with the	Exhibit No. E-4
(a) the proposed transmitter location, and the	radials along with p	profile graphs have been	prepared;	
(b) the 1 mV/m predicted contour and, is commercial channel, the 3.16 mV/m contour;		educational applicants	i applying on a	
(c) the legal boundaries of the principal comm	unity to be served			
<ol> <li>Specify area in square kilometers (1 sq. mi, predicted 1 mV/m contour,</li> </ol>	= 2.59 sq. km)	and population (latest c	ensus) within the	
Area 13 737 sq. km.	Population _	60 010		
16. Attach as an Exhibit a map (Sectional Aeronau) posed 1 mV/m (60 dbw) contours. PRESENT AREA = 9213 SQ. KM.	tical charts where	ebtainable/showing the	present and pro-	Exhibit No. E-4
Enter the following from Exhibit above:	Gain Area	4524	_ sq. m/L KM	
-	Loss Area	0	sq. mil KM	
Percent change (gain area plus loss area as p	arcanisms of speci	+49.1	<b>%</b> .	
If 50% or more this constitutes a major char	•		-	
		•		

For an application involving an auxiliary facility only, attach as an Exhibit a map (Sectional Aereneutical Chart or equivalent) that shows clearly, legibly, and accurately, and with latitude and longitude markings and a scale of distance in kilometers:  (a) the proposed auxiliary 1 mV/m contour; and  (b) the 1 mV/m contour of the licensed main facility for which the applied-for facility will be auxiliary. Also specify the file number of the license. See 47 C.F.R. Section 73,1675. (File No.:						
(Source:						
Other Ibrie	fly summarizel					
Radial bearing (degrees True)	Height of radiation center above average elevation of radial from 3 to 16 km (meters)	Predicted Distances to the 1 mV/m contour 60 DBU (kilometers)				
0	603.2	63.2				
45	644.1	64.8				
90	554.8	61.1				
135	714.8	67.3				
180	751.4	68.5				
225	728.8	67.8				
270	749.2	68.4				
315	747.1	68.4				

If Yes, attach as an Exhibit a showing of compliance with all provisions of the Agreement between the United States of America and the United Mexican States concerning Frequency Modulation Broadcasting

19, is the proposed antenna location within 320 kilometers (199 miles) of the common border between

Exhibit No.

Yes X No

FCC 340 (Page 15) February 1992

the United States and Mexico?

in the 88 to 108 MHz band.

20.	is the proposed antenna location within 320 kilometers of the common border between the United States and Canada $^{\circ}$	Yes X No
	If Yes, attach as an Exhibit a showing of compliance with all provisions of the Working Agreement for Allocation of FM Broadcasting Stations on Channels 201-300 under The Canada-United States FM Agreement of 1947.	Exhibit No.
21.	If the proposed operation is for a channel in the range from channel 201 through 220 (88.1 through 91.9 MHz), or if this proposed operation is for a class D station in the range from Channel 221 through 300 (92.1 through 107.9 MHz), attach as an Exhibit a complete allocation study to establish the tack of prohibited overlap of contours with other U.S. stations. The allocation study should include the following:	Exchibit No. E-5
	<ul> <li>(a) The normally protected interference—free and the interfering contours for the proposed operation along all azimuths.</li> <li>(b) Complete normally protected interference—free contours of all other proposals and existing stations to which objectionable interference would be caused.</li> <li>(c) Interfering contours over pertinent arcs of all other proposals and existing stations from which objectionable interference would be received.</li> <li>(d) Normally protected and interfering contours over pertinent arcs, of all other proposals and existing stations, which require study to show the absence of objectionable interference.</li> <li>(e) Plot of the transmitter location of each station or proposal requiring investigation, with identifying call letters, file numbers and operating or proposed facilities.</li> <li>(f) When necessary to show more detail, an additional allocation study will be attached utilizing a map with a larger scale to clearly show interference or absence thereof.</li> <li>(g) A scale of kilometers and properly labeled longitude and latitude lines, shown across the entire Exhibit(s). Sufficient lines should be shown so that the location of the sites may be verified.</li> <li>(h) The name of the map(s) used in the Exhibit(s).</li> </ul>	
	. With regard to any stations separated by 53 or 54 channels (10.6 or 10.8 MHz) attach as an Exhibit information required in 1/ Iseparation requirements involving intermediate frequency (i.f.) interference).	Exhibit No. E-5
23.	(a) Is the proposed operation on Channel 218, 219, or 220?	Yes X No
	(b) If the answer to (a) is yes, does the proposed operation satisfy the requirements of 47 CFR. Section 73.207?	Yes No
	(c) If the answer to (b) is yes, attach as an Exhibit information required in 1/ regarding separation requirements with respect to stations on Channels 221, 222 and 223.	Exhibit No.
	(d) If the answer to (b) is no, attach as an Exhibit a statement describing the short spacing(s) and how it or they arose.	Exhibit No.
	•	

1/ A showing that the proposed operation meets the minimum distance separation requirements, include existing stations, proposed stations, and cities which appear in the Table of Allotments; the location and geographic coordinates of each antenna, proposed antenna or reference point, as appropriate; and distance to each from proposed antenna location.

### SECTION V-B - FM BROADCAST ENGINEERING DATA (Page 6)

(e) If authorization pursuant to 47 CF.R. Section 73.215 is requested, attach as an Exhibit a complete engineering study to establish the lack of prohibited overlap of contours involving affected stations. The engineering study must include the following: DOES NOT APPLY.	Exhibit No.
<ol> <li>Protected and interfering contours, in all directions (360 ), for the proposed operation.</li> <li>Protected and interfering contours, over pertinent arcs, of all short-spaced assignments, applications and allotments, including a plot showing each transmitter location, with identifying call letters or file numbers, and indication of whether facility is operating or proposed. For vacant allotments, use the reference coordinates as transmitter location.</li> <li>When necessary to show more detail, an additional allocation study utilizing a map with a larger scale to clearly show prohibited overlap will not occur.</li> <li>A scale of kilometers and properly labeled longitude and latitude lines, shown across the entire exhibit(s). Sufficient lines should be shown so that the location of the sites may be verified.</li> <li>The official title(s) of the map(s) used in the exhibits(s).</li> </ol>	
24. Is the proposed station for a channel in the range from Channel 201 to 220 (88.1 through 91.9 MHz) and the proposed antenna location within the distance to an affected TV Channel 6 station(s) as defined in 47 CF.R. Section 73.525?	Yes X No
If Yes, attach as an Exhibit either a TV Channel 6 agreement letter dated and signed by both parties or a map and an engineering statement with calculations demonstrating compliance with 47 CF.R. Section 73.525 for each affected TV Channel 6 station.	Exhibit No.
25. Is the proposed station for a channel in the range from Channel 221 to 300 (92.1-107.9 MHz)?	Yes X No
If Yes, attach as an Exhibit information required in 11. (Except for Class B (secondary) proposals.)	Exhibit No.
26. Environmental Statement (See 47 C.F.R. Section 1.130) et seq.)	
Would a Commission grant of this application come within Section 1.1307 of the FCC Rules, such that it may have a significant environmental impact?	Yes X No
If you answer Yes, submit as an Exhibit an Environmental Assessment required by Section 1.1311.	Exhibit No.
If No, explain briefly why not. SEE EXHIBIT E-6	
CERTFICATION	
I contifu that I have presented this Continued this confliction on behalf of the confliction and that often such present	annestina I have

I certify that I have prepared this Section of this application on behalf of the applicant, and that after such preparation, I have examined the foregoing and found it to be accurate and true to the best of my knowledge and belief.

Name (Typed or Printed) ROBERT A. McCLANATHAN, P.E. McCLANATHAN AND ASSOCIATES, INC.	Relationship to Applicant le.g., Consulting Engineer!  PROFESSIONAL ELECTRICAL ENGINEER
Signature	Address linciple 219 Code1
R.a. 77 a Clanothan	P.O. Box 939 PORTLAND, OR 97207
Date	Telephone No. Iinclude Area Eadel
JUNE 16, 1992	(503 ) 246-8080

#### McCLANATHAN and ASSOCIATES, INC.

PROFESSIONAL ELECTRICAL ENGINEERS
P.O. BOX 939 - PORTLAND, OREGON 97207-0939
TEL: (503) 246-8080 FAX: (503) 246-6304

#### ENGINEERING STATEMENT

for

#### STATE OF OREGON ACTING BY AND THROUGH THE STATE BOARD OF HIGHER EDUCATION

KSKF, Klamath Falls, Oregon

FCC Form 340, Section V-B

This statement and attached exhibits have been prepared for State of Oregon acting by and through the State Board of Higher Education relative to application to modify the construction permit for NCE FM broadcast station KSKF in Klamath Falls, Oregon.

The existing FCC permit, BPED-870121MB and BMPED-880415MC authorize construction on 90.0 mHz, FM channel 215, with an effective radiated power of 2.0 kilowatts horizontal and 1.65 kW vertical polarization. It is proposed to increase the antenna power to 6.5 kW horizontal and 2.0 kW vertical polarization. No other changes are requested. The presently authorized facilities have been constructed and application for license has been tendered, BLED-890821KA.

Exhibit E-1 is a sketch of the existing KSKF tower. The proposed antenna will be a four section elliptically polarized antenna, side mounted at the same vertical position as the existing four section antenna.

Exhibit E-2 is a statement by the Applicant accepting full responsibility for elimination of any objectionable interference to existing communications services if such should occur from the proposed operation.

Exhibit E-3A, a full scale portion of the 7.5 minute Lost River Geological Survey map, shows the existing KSKF tower location. There are no AM broadcast stations located within two miles of the FM antenna site. Exhibit E-3B is a reduced scale copy of the complete Lost River 7.5 minute topographic quadrangle map.

Exhibit E-4 shows the present and proposed 1.0 mV/m, 60 dBu contours. The area within the proposed 60 dBu contour is 49.1 percent greater than the present contour. All of the corporate city of Klamath Falls is located within the 60 dBu contour and is line-of-sight from the proposed antenna location.

Census facts for the population of the area enclosed within the proposed 60 dBu contour was provided by Dataworld, Inc. and is based on the 1990 U.S. Census. The areas within

the 60 dBu contours were measured with a compensating polar planimeter.

Exhibit E-5 is the frequency allocation study for FM channel 215. With the single exception of a new application on Ch. 215C2 at Redding, California, this study shows that there is no co-channel or adjacent channel FM station or Ch. 6 TV station that deserves detailed study since distance clearances between proposed and protected contours are considerable. The proposed increase in effective radiated power for KSKF is mutually exclusive with the application in Redding, FCC File No. BPED-920316ME and amendment 920528MA, since there is a prohibited overlap of contours specified in 47 C.F.R. 73.509(a). The cut-off date for the Redding application, BPED-920316ME, is July 2, 1992, FCC Report No. A-238.

Exhibit E-6 is a statement describing how the Applicant will comply with ANSI and FCC specified guidelines for human exposure to radio frequency radiation.

Since the Applicant proposes to increase antenna power, FAA Form 7460-1 has been prepared and submitted to the regional FAA office in Renton, Washington.

Respectfully submitted,





Robert A. McClanathan, P.E. McClanathan and Associates, Inc. Professional electrical Engineers

June 16, 1992

ROBERT A. McCLANATHAN, being duly sworn upon oath, deposes and says:

- 1. That he is President of McClanathan and Associates, Inc., Professional Electrical Engineers.
- 2. That he is a licensed Professional Electrical Engineer in the States of California, Oregon, Washington and the District of Columbia and that he is a member of the Association of Federal Communications Consulting Engineers.
- 3. That he has been engaged in radio and television broadcast engineering and developments since 1955.
- 4. That he has been retained by State of Oregon acting by and through the State board of Higher Education to prepare the engineering exhibits relative to application to modify the FM construction permit for NEC FM broadcast station KSKF in Klamath Falls, Oregon, on channel 215C1.

Affiant finally states that the material and exhibits contained in this report were prepared by him or under his direct supervision and that he has checked all results and believes them to be true.

Robert A. McClanathan, P.E.

Subscribed and sworn to before me this 16th day of June, 1992.



Rasbara Mc Ucuatha Notary Public, Oregon

In and for the County of Multnomah, State of Oregon.


# INDEX TO EXHIBITS

<u>EXHIBIT</u>	TITLE
E-1	Vertical Sketch of Existing KSKF Tower and Four Section FM Antenna
E-2	Statement Concerning Radio Frequency Interference
E-3A	Transmitter Location Plotted on 7.5' USGS Map
E-3B	Reduced copy of Lost River, Oregon 7.5' USGS Map
E-5	Map of Present and Proposed 1 mV/m, 60 dBu Contours
E-6	Environmental Statement Concerning Human Exposure to Radio Frequency Radiation

VERTICAL PLAN SKETCH OF EXISTING KSKF

FM ANTENNA AND SUPPORTING TOWER

KLAMATH FALLS, OREGON



# MCCLANATHAN & ASSOCIATES

CONSULTING BLECTRONIC ENGINEERS

P. O. BOX 939


PORTLAND, OREGON 97207


## STATEMENT CONCERNING RADIO FREQUENCY INTERFEREENCE


The existing four section FM antenna is side mounted at the top of a 49.7 meter high guyed steel tower. The existing antenna ERP is 2.0 kilowatts with circular polarization. It is proposed to increase the antenna power to 6.5 kW in the horizontal polarization with the vertical polarization remaining at 2.0 kW ERP.

Because of the relatively low antenna power, it is believed that there will be no adverse effect on existing communications facilities located in the vicinity. The existing 2.0 kW ERP operation on 90.9 mHz has not caused any known interference to other radio communications. In the unpredictable event that intermodulation or other interference should occur as a result of the proposed operation, the Applicant accepts responsibility to immediately take action to correct such adverse conditions by means of standards types of cavity filters and traps.

LOST RIVER QUADRANGLE
OREGON—CALIFORNIA
7.5 MINUTE SERIES (TOPOGRAPHIC)







# McClanathan & Associates, Inc. Portland, Oregon

Page 1 June 16, 1992

## FM Interference study

Title: KSKF Channel 215C1 ( 90.9 MHz) ERP: 6.50 kW; EAH: 6 Database: FCC 04/28/92	Latitude: 42-05-50 Safety zone: 130 km
Call Auth Licensee name Chan ERP City of License St FCC File no. Freq EAH	<pre>I-m Longitude -from (km) (km)</pre>
	40-43-36 232.8 247.8 161.6
KIBC LIC Burney Educational B/Cin *213C3 .  Burney	F(50,50) 4.8 61.00 CLEAR $F(50,50)$ 60 dBu = 29.23 km
	514 123-31-17 24.4 227.0 CLEAR F(50.50) 60 dBu = 52.37 km
KSKF CP State of Oregon *215C1 Klamath Falls OR 90.9 6 Proposed F(50,10) 40 dBu = 149.1 km; KSKF Proposed F(50,50) 60 dBu = 66.29 km; KSKF	F(50,50) 60 dBu = 54.43 km
NEW APC California State Univers *215C2 .  Redding CA 90.9 10  Proposed F(50,10) 40 dBu = 149.1 km; NEW  Proposed F(50,50) 60 dBu = 66.29 km; NEW	(10.50) 122-38-58 26.7 -14.9 SHORT $(10.50)$ 60 dBH = 52.34 km
KWAX       CP       Oregon       State Board of Hi       *216C1 21         Eugene       OR       91.1 3         Proposed F(50,10)       54 dBu = 97.63 km; KWAX         Proposed F(50,50)       60 dBu = 66.29 km; KWAX	370 123-06-45 149.9 83.91 CLEAR
KWAX       LIC       Oregon       State Board of Hi       *216C1         Eugene       OR       91.1       3         Proposed F(50,10)       54 dBu = 97.63 km; KWAX         Proposed F(50,50)       60 dBu = 66.29 km; KWAX	308 123-06-53 149.9 88.94 CLEAR
KIDE LIC Hoopa Tribal Broadcastin *217A .  Hoopa CA 91.3 -4  Proposed F(50,10) 80 dBu = 26.58 km; KIDE  Proposed F(50,50) 60 dBu = 66.29 km; KIDE	174 123-41-05 55.4 137.5 CLEAR
KSRS LIC St. of or Acting/St.Bd o *218A Roseburg OR 91.5 Proposed F(50,50) 100 dBu = 5.096 km; KSRS Proposed F(50,50) 60 dBu = 66.29 km; KSRS	F(50,50) 60 dBu = 21.27 km
KEKA-FM LIC Eureka Broadcasting Comp 268C Eureka CA BLH-831212AA 101.5 6 DOC-82-749	89 40-25-12 228.5 277.2 41 525 124-05-00 46.9 236.2 CLEAR
	39-35-03 150.5 319.1 22 119-47-52 331.7 297.1 CLEAR 03KC

#### ENVIRONMENTAL STATEMENT

An Environmental Assessment (EA) is categorically excluded under 47 C.F.R. Section 1.1306(b) of the FCC Rules and Regulations since the Applicant's proposal does not:

- 1. Involve a site location specified under 47 C.F.R. Section 1.1307(a)(1) through (7).
- 2. Involve high intensity lighting under 47 C.F.R. Section 1.1307(a)(8).
- 3. Result in human exposure to radiofrequency radiation in excess of the applicable safety standards specified in 47 C.F.R. Section 1.1307(b), (ANSI C95.1-1982 and ANSI C95.1-1991).

The Maximum Permissible Exposure (MPE) for uncontrolled environments at 90.9 mHz is 0.2 mW/cm<sup>2</sup>. The distance D from the proposed FM antenna radiating a total of 8.5 kW (6.5 H and 2.0 V) ERP to the MPE point may be determined by the equation on page 9 of the FCC OST Bulletin No. 65 dated October 1985. The relative field strength at depression angles towards the ground for a four section antenna, as shown on the attached vertical field strength profile graph, will be less than 0.29. The MPE distance from this antenna for uncontrolled exposure is:

$$D^{2} = \frac{(2.56)(1.64)(0.29)^{2}(8,500 \text{ watts})(1000 \text{ mW/W})}{4(3.1416)(0.2 \text{ mW/cm}^{2})}$$

D = 1093 cm = 10.9 meters

The center of radiation for the four section FM antenna is 43.3 meters above ground level. Therefore, the proposed KSKF installation does comply with ANSI and FCC specified guidelines for uncontrolled human exposure to radio frequency radiation.

The Applicant owns the radio tower and associated equipment building and leases transmitter space in the building and antenna positions on the tower to other communications users. Collocated at this site are the transmitters for KLAD-FM, 63 kW ERP, KDKF TV, Ch. 31, 6 kW ERP and KFTS TV, Ch. 22, 9.33 kW ERP. Theoretical calculations of the total combined radio frequency field intensity at any point with acceptable accuracy is just not possible due the numerous RF sources, uncertain antenna radiation patterns and radiation reflections from tower, and building structures. Only on-site field intensity measurements will determine if any areas exceed the FCC

specified guidelines for human exposure to radio frequency radiation.

The Applicant proposes to measure the radio frequency field intensity with appropriate instruments during the equipment test period to determine what ground and building areas and heights on the tower experience levels that exceed the specified guidelines for human exposure to radio frequency radiation as described in OST Bulletin No. 65 and the American National Standard ANSIC95.1-1991. Such areas and heights on the tower that exceed the MPE for controlled exposure will be posted at the transmitter and tower facility.

The Applicant has a written condition in their agreement with lessees which requires that maintenance personnel terminate all RF emissions from the FM and TV antennas during any time when climbing the tower is necessary for inspections or maintenance within these posted areas. The licensee will post signs at the tower site stating "CAUTION - High Level Radio Frequency Energy Area - NO TRESPASSING". The tower structure will be fenced to prevent unauthorized access.

The area where the tower is located is a very remote site on Stukel Mountain not frequented by public visitors. There are two gates on the road to the site to limit access to authorized personnel. The tower area at the top of Stukel Mountain is confined along a narrow ridge. Where possible, all ground level areas that exceed specified maximum field intensity levels, as determined by measurements, will be fenced and posted with caution signs as described above. However, large area fencing around the tower is not practical. Therefore, if on-site measurements determine there are ground level areas where the total radio frequency power density exceeds the MPE for uncontrolled exposure that can not be fenced, the Applicant will post warning signs at the MPE boundary.

The Applicant believes there will be no significant effect on the human environment regarding public exposure or occasional visits by technical personnel and that fences and warning signs will be sufficient for proper notification of a potential hazard. The Applicant and its lessees understand that interruptions to normal radio transmissions will be necessary when maintenance personnel must work in posted areas on the ground and tower.

ELEVATION PATTERN DATE: JUNE 16, 1992 BEAM TILT= 0% JMEP-4 RMS GAIN= 1.61 NULL FILL= 0%

PLOT PREPARED FOR: KSKF FREQ: 90.9 mHz

PLOT PREPARED FOR:		R:	KSKr							FREQ: 90.9 m			
ELEVATION	FIELD		. 1	. 2	. 3	. 4	. 5	.6	.7	. 8	.9	1.	0
10.00	.389	:	-+-	+	+	++	+	+	+	+	+	+	
8.00	.575	:						*					
6.00	.745	:							*				
4.00	.881	:									*		
2.00	.970	:										*	
0.00	1.000	:	-+-	+	+	+	+	+	+	+	+	+	
-2.00	.970	:										*	
-4.00	.881	:									*		
-6.00	.745	:							*				
-8.00	.575	:						*					
-10.00	.389	:				*							
-12.00	.205	:		*									
-14.00	.039	: *											
-16.00	.095	:	*										
-18.00	.188	:		*									
-20.00	.236	:			k								
-22.00	.243	:		1	k								
-24.00	.213	:		*									
-26.00	.156	:		*									
-28.00	.082		*										
-30.00	.004	*											
-32.00	.068	: *											
-34.00	.128	:	*										
-36.00	.169	:		*									
-38.00	.189	:		*				*					
-40.00	.187	:		*									
-42.00	.165	:		*									
-44.00	.128	:	*										
-46.00	.079	:	*										
-48.00	.024	: *											
-50.00	.034	: *											
-52.00	.090	:	*										
-54.00	.142	:	,	*									
-56.00	.186	:		*									
-58.00	.223	:		*									
-60.00	.250	:		t	k								
-62.00	.269	:			*								
-64.00	.279	:			*								
-66.00	.283	:			*								
-68.00	.280	:			*								
-70.00	.273	:			*								
-72.00	.262	:			. <b>*</b>								
-74.00 -76.00	.248	:		t t									
-78.00 -78.00	.233	:			π.								
-80.00	.217	:		*									
-82.00	.200	:		*									
-84.00	.184 .168	: :		*									
-86.00	.153	:		*									
-88.00	.133	:		*									
-90.00	.125	:	*										
20.00	. 163	•	^										